Monitoring & Follow-up
General Contracting Est.
CR. 2051047477

MOFCO

مؤسسة الرصد والمتابعة
للمقاولات العامة
س.ت ٢٠٥١٠٤٧٤٧٧

هامات
hamat

QUOTATION

Mall	kadi mall	**Ref No**	RMC-HM-2026-1644
Project	Fire Fighting Network Repair Works	**Date**	06/10/26

S/N	DESCRIPTION	Unit	QTY	Unit Price	Total
1	Cutting and removing asphalt and excavating to a depth of two meters to expose the firefighting line (including debris disposal and the provision of traffic safety barriers); followed by the supply and placement of clean sand and water.	LM	280	145	40,600
2	Asphalt reinstatement works for trenches at the Required areas as per their width. Includes spraying liquid asphalt coats (MC1 & RC2); supplying, laying, and compacting asphalt layers. All quantities mentioned are approximate and may vary.	M2	260	68	17,680
3	Inspection and repair of HDPE pipe at the intersection joints, including supply and installation of certified European fittings (elbows, tees, couplings, etc.). Materials will be sourced from or approved by Al-Wasaiel or Al-Munif.	PC	5	1450	7,250
4	Inspection and repair of the HDPE pipeline, including running lines with interval joints, including supply and installation of certified European fittings (couplings, pipe pieces, etc.). Materials will be sourced from or approved by Al-Wasaiel or Al-Munif.	PC	2	950	1,900
5	Supply and install a high-specification pressure gauge assembly. The unit includes an approved WIKA liquid-filled (Glycerin) pressure gauge (0-10 Bar / 0-140 psi, EN 837-1, Class 1.6) with a stainless steel case. The assembly must be integrated with a premium grade stainless steel (SS 316) pigtail syphon tube, a heavy-duty stainless steel isolation ball valve, and all necessary SS fittings (elbows, nipples) for a complete, vibration-resistant, and leak-proof installation.	PC	9	928	8,352
Total Amount of Works					**75,782**

Technical Specifications & Payment Terms	
Excavation & Safety	Asphalt cutting, 2m digging, barriers, and clean sand backfill.
Asphalt Works	MC1/RC2 coats, laying, and compacting asphalt layers.
HDPE Pipe	Inspection, pipe repairs, and European certified fittings.
Pressure Gauges	German WIKA glycerin pressure gauges with SS316 pigtail syphons and isolation valves.
Warranty	One (1) year warranty on the complete works from the date of handover.

We look forward to a successful collaboration

MOFCO C.R. 2051047477 KHOBAR Monitoring & Follow-up Gen. cont. Est